



PASCHIM MEDINIPUR REGIONAL OFFICE
SAMMRIDDHI APARTMENT, P.O. MIDNAPORE,
DIST. PASCHIM MEDINIPUR- 721101.
PHONE :- 03222-274529 FAX:-03222-275620.
E-mail:- ropasmib@bgvbank.co.in , rmpasmid@bgvb.co.in

Ref: BGVB/RO/PAS.MED/ 2423 /2021

DATE: 08.12.2021

NOTICE

INVITING TENDER FOR SUPPLY & INSTALLATION OF ELECTRICAL WORKS FOR REGIONAL OFFICE & MIDNAPORE BRANCH UNDER PASCHIM MEDINIPUR REGION

Bangiya Gramin Vikash Bank invites sealed tenders from Bank approved suppliers to SUPPLY & INSTALLATION OF ELECTRICAL WORKS ALONG WITH LAN for Regional Office & Midnapore Branch under PS – Medinipur , Keranitola, Dist Paschim Medinipur, PIN- 721101 as per work schedule and specification considering the following terms and conditions. Specification of works are given in the format.

- 1) The tender must be sealed and to be submitted within **16th December 2021** within the banking hours at SAMMRIDDHI APARTMENT, P.O. MIDNAPORE, DIST. PASCHIM MEDINIPUR- 721101
- 2) After the scheduled date and time no Offer will be accepted regarding the matter.
- 3) The offered rate will be opened on **17th December 2021** at 12.30pm. Quoter in person or his representative may be present at the time of opening of rates.
- 4) No further correspondence will be entertained regarding the matter.
- 5) Regional Manager has the right to cancel or reject the offered rate without assigning any reason and cause.
- 6) Rate must be quoted in the prescribe format only. No other format or alteration/deviation will be entertained and will be rejected.
- 7) 10% caution money may be deposited for one year against the offered rate as security and no interest will be attract there against.
- 8) For any defect detected after installation, supplier will have to replace/repair the same on his own cost.
- 9) No compromise will be entertained with quality of the material and quality of work.
- 10) Proposed time for completion of the work should be mentioned in the quotation.

By Order,

Yours faithfully,

For & on behalf of
Bangiya Gramin Vikash Bank


Regional Manager
Paschim Medinipur


Regional Manager,
Paschim Medinipur Region.

Dated :- 08.12.2021

Sub: Quotation for Earthing & Electrical Wiring for CBS related Single Phase Wiring of on line UPS

Sl. No	Particulars	Rate	Qty.	Amount
1	<u>COMPUTER POWER BOARD MAIN LINE</u> Supply of new computer power wiring 1x3 nos multicoil core 1.5sq. mm with Finolex Com.(copper wire) separate phase neutral and earthing enclose 20mm. PVC stick pipe and 20mm PVC saddle and 25mm flexible pipe with PVC gland circuit D/B to computer power board main line wiring complete fitting and fixing etc (Make by Finolex)			
2	<u>UPS INPUT OUTPUT MAIN LINE</u> Supply of new 1x2 nos. 6sq. mm Finolex Com. (copper wire) separate phase neutral and 1x1x 4sq. mm Finolex com. earthing enclose 20mm. PVC (ISI)stick pipe and 20mm PVC saddle and 25mm flexible pipe with PVC gland UPS output input main line wiring complete fitting and fixing.(Make by Finolex)			
3	<u>COMPUTER POWER SWITCH BOARD</u> Supply of new 8/10 inch special galvanized (GI) board and 9/11 inch 4mm fiber top enclose 6 amp. 5 pin 4 nos. Prity Com with 6 amp. Single way switch 4 nos. Prity Com. And 10 amp. Integrated lamp1 No. and 10 amp. Board fuse 1 nos. Prity Com 1 inch brash screw with washer Complete fitting and fixing.(Make Pritam Prity, for all switch, plug, indicator board fuse)			
4	<u>COMPUTER CIRCUIT D.B</u> Supply of new circuit D/B 6way SPN single door (distribution box) with 10 amp. single pole MCB (Miniature circuit braker) 6 nos. complete fitting and fixing. (Make by Havels)			
5	<u>UPS OUTPUT ISOLATOR</u> Supply of new 4 way SPN single door D/B(Distribution Box) with 40amp. DP incoming isolator 2 nos. complete fitting and fixing (Make by Havels)			
6	<u>UPS OUTPUT MCB D.B</u> Supply of new 4 way SPN single door D/B(Distribution Box) with 40amp. DP (double pole) MCB 2 nos. complete fitting and fixing (Make by Havels)			
7	<u>UPS-1 -- UPS-2 BYPASS CHANGEOVER</u> Supply of new 32amp. 4 pole change over switch (Make by Havels)			
	Balance c/f			
	Balance b/f			
8	<u>UPS INPUT D.B</u> Supply of new 2+4 way SPN D/B(Distribution Box)with 40amp. DB isolator 2 nos. and 63 amp. incoming isolator 1nos. complete fitting and fixing (Make by Havels)			
9	From UPS 1 and UPS 2 bypass connection complete fitting and fixing (Make by Havels.)			

Sl. No	Particulars	Rate	Qty.	Amount
10	<u>CBS Process Earthing</u> Supply new 300mm x 300mm x 3mm thick Copper plate Electrode to be installed so that its top graded shall be at a minimum of depth 3mtr. Below ground level after position of ground with charcoal and salt and connecting with 1/2 inch P.V.C pipe with 6mm copper earth lead in upto 10mtr. length by bolting and brazing to the G.I bolts and suitable length double nuts and washers including supply and fitting with water arrangements 19mm P.V.C pipe after portion 30cm x 30cm cast iron hanged to iron frame water funnel and and connected manhole chamber complete fitting and fixing etc. as below:			
11	<u>EARTH BAR TO INPUT D.B RUNNING EARTHINH</u> Supply of new running earthing 4.0 sq. mm copper wire enclose with 20mm. PVC stick pipe and 20mm PVC saddle and 25mm flexible pipe fitting fixing complete.(Make Finolex)			
12	<u>BRANCH HEAD MAIN SWITCH</u> Spplly of New 63 amp . Single phase DP power main switch with suitable size iron frame and suitable size G.I nuts & bolts with washer complete fitting and fixing etc. (Make Havels)			
13	<u>C.A. fuse</u> (if not included in quotation of WBSEDCL in connection with supply Addl. Load) Supply of new 63amp CA cut out (Make Flora)			
14	<u>Full load Branch Generator and Electric Change Over -</u> Supply of new 63 amp Single Phase change over switch suitable size iron frame and suitable size G.I nuts & bolts with washer complete fitting and fixing etc.te. Make BenteK			
Total				Rs. -

For & on behalf of
Bangiya Gramin Vikash Bank

Regional Manager
Paschim Medinipur

Sub: Quotation for Cash counter wiring material supply, fitting & fixing

Sl. No	Particulars	Rate	Qty.	Amount
1	Distribution wiring 3 x 1.5sq. mm single multistand copper wire (phase, nutral, earth) through 20mm. PVC rigid conduit pipe including supply all materials i.e. saddle scrw, elbow flexible pipe etc. complete as required.			
2	Supply and fixing of new 4"X10" wooden board and including supply of all materials i.e. bakelite top cover, 6A plug, 2Nos, 10A Cutout 1 No, 6A Switch 5Nos.etc. and inter connection complete as required.			
3	Supply and fixing 20mm P.V.C Cercular box with Angle Holder and Suitable size screw complete as required.			
Total				Rs. -

For & on behalf of
Bangiya Gramin Vikash Bank


Regional Manager
Paschim Medinipur

Quotation

Sub: Quotation for supply materials and fixing the same for computer link line.

Sl. No	Particulars	Rate	Qty.	Amount
1	Distribution new wiring to link line to the different computer board including the supply fixing materials as Cat -6 wire through 20mm PVC rigid conduit on wall by shaddle support within it inter connection, testing checking of C.B.S system complete as required.			
Total				Rs. -

For & on behalf of
Bangiya Gramin Vikash Bank

Regional Manager
Paschim Medinipur