



MURSHIDABADREGION  
48, NAYA SARAK ROAD  
P.O.: BERHAMPORE  
DIST: MURSHIDABAD

TENDER NOTICE NO: 05 /2023

Date: 13.03.2024


**Notice inviting quotation/rate for refurbishing work for installation of Air Condition machine of our Aurangabad/Jangipur/Sammatinagar/Bhakuri/ Kandi Zemo Bazar & Murshidabad Regional Office Branch (06 offices)**

Sealed quotations are invited for seeking rates of the refurbishing work as per sketched map attached herewith on or before **27.03.2024**.

The interested firms/ vendors can either submit their quotation in person to Regional Office Murshidabad (at Letter Receive Section) on any working day during office hours or may send by post so that the same reaches this office within the stipulated date. The quotations will be opened at R.O. on **28.03.2024 at 12:00 Noon**. The interested firms/ vendors may be present during opening of such quotations.

***Terms and conditions***

1. Quotation Rate will be considered on Lower Rate basis. Materials are to be supplied with a sharing basis of 60:40 between L1 and L2 bidder, provided L2 bidder agrees to supply at the lowest quoted rate. In case of dissent from L2 bidder, Bank's decision will be final.
2. Rates are to be quoted as per work schedule attached herewith  
Firms must have GST registration number.
3. After expiry of the above time schedule no quotation will be accepted.
4. Bank reserves the right to accept or cancel bid unilaterally without assigning any reason thereof, prior to placement of supply order/signing of contract thereby incurring any liability to the affected bidder(s) or any obligation to inform the affected bidder(s) for the cause of banks action and no further correspondence will be entertained regarding the matter.
5. Supply of the articles is to be made in due time and any deviation/delay may attract penalty from original bill.
6. Selected vendor will have to finish the stipulated work in due time. Otherwise they will be debarred from getting order for their other selected items and/or their further participation in the tender process may be suspended.
7. The rate/s will be inclusive of delivery charges & others but exclusive GST.
8. Materials will be rejected if any defect/deviation in quality from specification is found as given in tender process.

  
**Regional Manager**



**BUDGETARY ESTIMATE INTERIOR AND FIXTURE WORK AT R.O. OFFICE**

S.L.	PARTICULAR	UNIT	QUANTITY	RATE	AMOUNT
1	MAIN ENTRANCE DOOR WITH FIXED PARTLY GLAZING PARTITION FOR BRANCH: Providing and fixing in position of door shutter, fixed partition and box partition attached with aluminium bar partly made of 8mm thick float glass and A.C.P. board as per design. The rates shall include cost of door frame, hardware, bolt, locks, hinges, handles etc. Door size: 3'-0" x 7'-0". and partition box size: 1'x 3'-5".(1nos.)and 1' x 7'-5"(2nos.) The rates shall include vinyl sticker pasting work the Bank's logo and emblem on the glass in the size and design as prescribed by the Bank.	S.F.T.	39.5		
2	ventilator.				
3	UPPER PORTION OF R.M.ROOM ,AND OFFICE AREA: Supply and fixing plyboard cover of out upper side lamination pasting finish work	NOS.	9nos.		
4	EXHAUST FAN DISMANTLE AND COVER WITH PLYBOARD IN THE PORTION	S.F.T.	111.5		
5	OFFICE AREA DOOR WITH FIXED PARTLY GLAZING PARTITION FOR BRANCH: Providing and fixing in position of door shutter, fixed partition and box partition attached with aluminium bar partly made of 8mm thick float glass and A.C.P. board as per design. The rates shall include cost of door frame, hardware, bolt, locks, hinges, handles etc. Door size: 3'-0" x 6'-0". The rates shall include vinyl sticker pasting work the Bank's logo and emblem on the glass in the size and design as prescribed by the Bank.	NOS.	6 nos.		
6	UPPER PORTION NEW PARTITION WORK WITH FRAME WORK:Supply of 6mm plyboard both side fix with wooden frame and lamination pasting finish work.	S.F.T.	18		
7	FULL HEIGHT PARTITION WORK: Supply of 6mm plyboard both side fix with wooden frame and lamination pasting finish work.	S.F.T.	9		
		S.F.T.	77		

*[Handwritten Signature]*



**BUDGETARY ESTIMATE INTERIOR AND FIXTURE WORK AT AURANGABAD BRANCH**

S.L.	PARTICULAR	UNIT	QUANTITY	RATE	AMOUNT
1	WINDOW COVERING WORK: window uper side block and cover with 6mm plywood fixing finish work. Window cover size: 5'x1' x 4 nos.	S.F.T.	20		
2	<p>MAIN ENTRANCE DOOR WITH FIXED PARTLY GLAZING PARTITION FOR BRANCH: Providing and fixing in position of door shutter, fixed partition and box partition attached with aluminium bar partly made of 8mm thick float glass and A.C.P. board as per design. The rates shall include cost of door frame, hardware, bolt, locks, hinges, handles etc.</p> <p>Door size: 3'-0" x 6'-5". fixed partition size: 3'-0" x 7'-0".(1nos.) and partition box size: 3'-0" x 6'-0".(1nos.)and 3'-0" x 7'-5"(2nos.) The rates shall include vinyl stickers pasting work the Bank's logo and emblem on the glass in the size and design as prescribed by the Bank.</p>	S.F.T.	103.5		

*[Handwritten signature]*





# **BUDGETARY ESTIMATE INTERIOR AND FIXTURE WORK AT KANDI ZEMO BRANCH**

S.L.	PARTICULAR	UNIT	QUANTITY	RATE	AMOUNT
1	MAIN ENTRANCE DOOR WITH FIXED PARTLY GLAZING PARTITION FOR BRANCH: Providing and fixing in position of door shutter, fixed partition and box partition attached with aluminium bar partly made of 8mm thick float glass and A.C.P. board as per design. The rates shall include cost of door frame, hardware, bolt, locks, hinges, handles etc. Door size: 3'-0" x 7'-0". fixed partition size: 3' x 7'-0". (1nos.) and partition box size: 6" x 6'-5".(1nos.)and 6" x 7'-5"(2nos.) The rates shall include vinyl sticker pasting work the Bank's logo and emblem on the glass in the size and design as prescribed by the Bank.	S.F.T.	53.5		
2	VENTILATORS COVER WORK: Supply and fixing plyboard cover of air pass ventilator.	NOS.	7 nos.		

*[Handwritten signature]*



**BUDGETARY ESTIMATE INTERIOR AND FIXTURE WORK AT JANGIPUR BRANCH**

S.L.	PARTICULAR	UNIT	QUANTITY	RATE	AMOUNT
1	<p>MAIN ENTRANCE DOOR WITH FIXED PARTLY GLAZING PARTITION FOR BRANCH: Providing and fixing in position of door shutter, fixed partition and box partition attached with aluminium bar partly made of 8mm thick float glass and A.C.P. board as per design. The rates shall include cost of door frame, hardware, bolt, locks, hinges, handles etc.</p> <p>Door size: 3'-0" x 7'-0". fixed partition size: 9' x 9'. (1nos.) and partition box size: 6" x 12'-5".(1nos.)and 6" x 8'-5"(2nos.) The rates shall include vinyl sticker pasting work the Bank's logo and emblem on the glass in the size and design as prescribed by the Bank.</p>	S.F.T.	117.5		
2	VENTILATORS COVER WORK: Supply and fixing plyboard cover of air pass ventilator.	NOS.	7 nos.		
3	BACK SIDE OF CASH COUNTER AREA DOOR: Supply and fitting 18mm ply door fixing attached with frame work. Door size:3'-0". x 7'-0".	S.F.T.	21		



# **BUDGETARY ESTIMATE INTERIOR AND FIXTURE WORK AT BHAKURI BRANCH**

S.L.	PARTICULAR	UNIT	QUANTITY	RATE	AMOUNT
1	MAIN ENTRANCE DOOR WITH FIXED PARTLY GLAZING PARTITION FOR BRANCH: Providing and fixing in position of door shutter, fixed partition and box partition attached with aluminium bar partly made of 8mm thick float glass and A.C.P. board as per design. The rates shall include cost of door frame, hardware, bolt, locks, hinges, handles etc. Door size: 5'-0" x 7'-0". The rates shall include vinyl sticker pasting work the Bank's <i>logo</i> and emblem on the glass in the size and design as prescribed by the Bank.	S.F.T.	35		
2	VENTILATORS COVER WORK: Supply and fixing plyboard cover of air pass ventilator.	NOS.	8nos.		
3	UPPER PORTION OF SAFE ROOM : Supply and fixing plyboard cover of out upper side safe room	S.F.T.	46.25		
4	EXHAUST FAN DISMANTLE AND COVER WITH PLYBOARD IN THE PORTION	NOS.	4 nos.		

*[Handwritten signature]*



**BUDGETARY ESTIMATE INTERIOR AND FIXTURE WORK AT SAMMATINAGAR BRANCH**

S.L.	PARTICULAR	UNIT	QUANTITY	RATE	AMOUNT
1	WINDOW COVERING WORK: window uper side block and cover with 6mm plywood fixing finish work. Window cover size: 5'x1' x 4 nos.	R.F.T.	65		
2	MAIN ENTRANCE DOOR WITH FIXED PARTLY GLAZING PARTITION FOR BRANCH: Providing and fixing in position of door shutter, fixed partition and box partition attached with aluminium bar partly made of 8mm thick float glass and A.C.P. board as per design. The rates shall include cost of door frame, hardware, bolt, locks, hinges, handles etc. Door size: 3'-0" x 6'-5". fixed partition size: 3' x 7'-5". (1nos.) and partition box size: 2'-5" x 6'-5".(1nos.)and 2'-5" x 7'-5"(2nos.) The rates shall include vinyl sticker pasting work the Bank's logo and emblem on the glass in the size and design as prescribed by the Bank.	S.F.T.	95.75		
3	ENTRANCE OF BATHROOM AREA DOOR: Supply and fitting 18mm ply door fixing attached with frame work. Door size:2'-5". x 6'-5".	NOS.	1 nos.		
4	VENTILATORS COVER WORK: Supply and fixing plyboard cover of air pass ventilator.	NOS.	10 nos.		

