



Purba Medinipur Regional Office
Sankarara, Tamluk
PO & DIST: Purba Medinipur
PIN-721636
Email: ropurbamib@bgvbank.co.in

Date : 20/05 /2023

Notice

**INVITING TENDER FOR SUPPLY, INSTALLATION AND TRANSFER OF ELECTRICAL WORKS FOR
JUKHIABAZAR BRANCH UNDER PURBA MEDINIPUR REGION**

- 1) Bangiya Gramin Vikash Bank invites sealed tenders from Bank approved suppliers to SUPPLY, INSTALLATION AND TRANSFER OF ELECTRICALWORKS FOR JUKHIABAZAR BRANCH UNDER PURBA MEDINIPUR REGION as per work schedule and specification considering the following terms and conditions. Specifications of works are given in the format. The tender must be sealed and to be submitted within 10th June 2023 within the banking hours at Purba Medinipur Regional Office , Sankarara, Tamluk Pin-721636.
- 2) After the scheduled date and time no offer will be accepted regarding the matter.
- 3) The offered rate will be opened on 12th June 2023 at 12.30 pm. Quoter in person or his representative may be present at the time of opening of rates.
- 4) No correspondence will be entertained regarding the matter.
- 5) Regional Manager has the right to cancel or reject the offered rate without assigning any reason.
- 6) Rate must be quoted in the prescribed format only. No other format or alteration/deviation will be entertained and will be rejected.
- 7) 10% caution money may be deposited for one year against the offered rate as security and no interest will be attracted against it.
- 8) For any defect has been detected after installation, supplier will have to replace/repair the same on his own cost.
- 9) No compromise will be accepted with quality of the material and quality of work.
- 10) Proposed time for completion of the work will be mentioned in the quotation.

By Order

Sd/-

Regional Manager,
Purba Medinipur Region
Hospital More, Tamluk.

Sub: Quotation for Earthing & Electrical Wiring for CBS related Single Phase Wiring of on line UPS.

Sl no.	Particulars	Rate	Qty	Amount
1	<u>COMPUTER POWER BOARD MAIN LINE</u> Supply of new computer power wiring 1X3 nosmulticoil core 1.5sq mm with Finolex Com.(copper wire) separate phase neutral and earthing enclose 20mm. PVC stick pipe and 20mm PVC saddle and 25mm flexible pipe with PVC gland circuit D/B to computer power board main line wiring complete fitting and fixing etc. (Made by Finole).			
2	<u>UPS INPUT OUTPUT MAIN LINE</u> Supply of new 1X2 nos. 6sq. mm Finolex Com. (copper wire) separate phase neutral and 1X1X4 sq mm Finolex Com. Earthing enclose 20mm. PVC (ISI) stick pipe and 20mm PVC saddle and25mm flexible pipe with PVC gland UPS output input main line wiring complete fitting and fixing. (Made by Finolex).			
3	<u>COMPUTER POWER SWITCH BOARD</u> Supply of new 8/10 inch special galvanized(GI) board and 9/11 inch 4mm fiber top enclose 6amp 5 pin 4 nos. Prity Com with 6amp Single way switch 4 nos. Prity Com. And 10amp Integrated lamp 1 no and 10 amp board fuse 1 no. prity com 1 inch brash screw with washer complete fitting and fixing. (Made by PritamPrity, for all switch, plug, indicator board fuse)			
4	<u>Computer Circuit D.B</u> Supply of new circuit D/b 6 way SPN single door (Distribution Box) with 10amp single pole MCB (Miniature circuit braker) 6 nos complete fitting and fixing (Made by Havells)			
5	<u>UPS OUTPUT ISOLATOR</u> Supply of new 4 way SPN single door D/B (Distribution Box) with 40amp DP incoming isolator 2 nos complete fitting and fixing (Made by Havells)			
6	<u>UPS OUTPUT MCB D/B</u> Supply of new 4 way SPN single door D/B (Distribution Box) with 40amp DP(Double pole) MCB 2 nos incoming fitting and fixing (Made by Havells)			
7	<u>UPS-1—UPS-2 BYPASS CHANGEOVER</u> Supply of new 32amp 4 pole changeover switch (Made by Havells)			
	Balance c/f			

	Balance b/f			
8	<u>UPS INPUT D/B</u> Supply of new 2+4 way SPN D/B with 40amp DB isolator 2 nos and 63 amp incoming isolator 1 nos complete fitting and fixing (Made by Havells)			
9	From UPS 1 and UPS 2 bypass connection fitting and fixing (Made by Havells)			
10	<u>CBS Process Earthing</u> Supply new 300mmX300mmX3mm thick Copper plate Electrode to be installed sothat its top graded shall be at a minimum of depth 3 mtr below ground level after position of ground with charcoal and salt and connecting with ½ inch PVC pipe with 6mm copper earth lead in upto 10 mtr length by bolting and brazing to thr GI bolts and suitable length double nuts and washers including supply and fitting with water arrangements 19mm PVC pipe after portion 30cm X30cm cast iron hanged to iron frame water funnel and connected manhole chamber complete fitting and fixing.			
11	<u>EARTH BAR TO INPUT D/B RUNNING EARTHING</u> Supply of new running earthing 4.0sq mm copper wire enclose with 20mm PVC stick pipe and 20 mm PVC saddle and 25mm flexible pipe fitting fixing complete (Made by Finolex)			
12	<u>BRANCH HEAD MAIN SWITCH</u> Supply of new 63amp single phase DP power main switch with suitable size iron frame and suitable size GI nuts and bolts with washer complete fitting and fixing etc (Made by Finolex).			
13	<u>C.A FUSE</u> (If not included in quotation of WBSEDCL in connection with supply Addl. Load) Supply of new 63amp CA cut out (Made by Flora)			
14	<u>FULL LOAD BRANCH GENERATOR AND ELECTRIC CHANGE OVER</u> Supply of new 63amp single phase change over switch suitable size iron frame and suitable sizeGI nuts and bolts with washer complete fitting and fixing etc (Made by Finolex).			
	<u>TOTAL</u>			RS.

Quotation for Cash Counter wiring material Supply, fitting and fixing.

Sl No.	Particulars	Rate	Qty	Amount
1	Distribution wiring 3X1.5 sq mm single multistand copper wire (phase, neutral, earth) through 20mm. PVC rigid conduit pipe including supply all materials i.e saddle screw, elbow flexible pipe etc completed as required.			
2	Supply and fixing of new 4"X10" wooden board and including of all materials i.e Bakelite top cover, 6A plug -20nos, 10A cutout-1 no, 6A switch – 5 nos etc and inter connection complete as required			
3	Supply and fixing 20mm PVC Circular box with Angle Holder and Suitable size screw complete as required			
	Total			Rs.



Purba Medinipur Regional Office
Sankarara, Tamluk
PO & DIST: Purba Medinipur
PIN-721636
Email: ropurbamib@bgvbank.co.in

Sub: Quotation for supplying materials and fixing the same for computer link line.

Sl No.	Particulars	Rate	Qty	Amount
1	Distribution new wiring to link line to the different computer board including the supply fixing materials as Cat-6 wire through 20mm PVC rigid conduit on wall by saddle support within it inter connection, testing checking of CBS system complete as required			
	Total			Rs.